## WISC DOT approved retaining wall system





## ReCon Wall System:


- Stong, wet cast blocks 1,457 to 4,088 lbs.
- 24" to 84" D x 48" W x 16" H
- Regular corner and cap blocks
- Half block (24" or 39" deep)
- Full fence or full high end/cap blocks
- Available in two unique faces

40 cycles, 5 of 5 samples

50 cycles, 4 of 5 samples

Compressive Strength Air Content (%)

- Gray color (stain applied after construction)
- Passed current WI DOT requirements.



·		REQUIREMENT Dry-cast Wet-cast	
TEST	METHOD		
Compressive Strength (psi)	ASTM C140	5000 min.	4000 min.
Air Content (%)	AASHTO T152	N/A	6.0 +/-1.5
Water Absorption (%)	ASTM C140	6 max. <sup>[3]</sup>	N/A
Freeze-Thaw Loss (%)	ASTM C1262 [1]	1.0 max. <sup>[2][3]</sup>	NI/A

ASTM C1262 [1]











7200 N. Broadway, Rochester, MN 55906 Phone: 507-288-8850 • Fax: 507-424-4697

1.5 max.[2][3]

## www.rochestercp.com

©Copyright 2018. All Rights Reserved. This information has been prepared for the benefit of customers interested in Rochester Concrete Products. It was reviewed carefully prior to publication. Rochester Concrete Products assumes no liability for its accuracy or completeness. Final determination of the suitability of any information or material for the use contemplated, or for its manner of use, is the sale responsibility of the user. S18

N/A

